
# COUNTY ROAD 32 INTERCHANGE - LONG LIST ALTERNATIVES



## **ALTERNATIVE 1 - PARCLO A2**

#### DESCRIPTION:


- Parclo A-2 interchange configuration
- Realignment of County Road 32 to the east for staging of replacement structure;
- Re-construction of existing ramps with improved radii

#### **ADVANTAGES**

- Additional weaving distance along Hwy 401 EB to Thousand Islands Pkwy relative to other options
- Lowest impacts to natural environment and potential for archaeological impacts;

#### DISADVANTAGES

- Less desirable left-turns required for northbound to eastbound and southbound to westbound movements resulting in increased collision risk and potential for operational issues;
- Reduced weaving distance along Hwy 401 WB to Thousand Islands Pkwy relative to Alternative 5;



## **ALTERNATIVE 2 - PARCLO A4**

#### DESCRIPTION:


- Parclo A-4 interchange configuration
- Realignment of County Road 32 to the east for staging of replacement structure;
- Addition of new directional on-ramps and re-construction of existing ramps with improved radii

#### ADVANTAGES

 Most desirable interchange configuration including improved operations and reduced collision risk with directional moves for all maneuvers

## DISADVANTAGES

- Reduced weaving distance along Hwy 401 EB and WB to Thousand Islands Pkwy relative to Alternatives 1 and 5;
   Moderate-High impacts to natural environment and potential for archaeological impacts relative to other
- Moderate-High impacts to natural environment and potential for archaeological impacts relative to other alternatives:
- Highest construction cost



## **ALTERNATIVE 3 - DIAMOND**

### DESCRIPTION:

Diamond interchange configuration

(REPLACEMENT WEST OF EXISTING

**CARRIED FORWARD** 

• Realignment of County Road 32 to the east for staging of replacement structure

#### <u>ADVANTAGE</u>

Slightly greater intersection / access spacing north of Highway 401 relative to other options

#### DISADVANTAGES

- Less desirable left-turns required for northbound to westbound and southbound to eastbound movements resulting in increased collision risk and potential for operational issues;
- Reduced weaving distance along Hwy 401 EB and WB to Thousand Islands Pkwy relative to Alternatives 1
  and 5
- Greatest impacts to natural environment and potential for archaeological impacts;



## ALTERNATIVE 4 - PARCLO AB TO EAST

## DESCRIPTION:

- Parclo AB interchange configuration with eastbound B-loop off-ramp
   Realignment of County Road 32 to the east for staging of replacement structure
- ADV/ANTA OF C

## ADVANTAGES

- Avoids eastbound speed change lane across Gananoque River bridge
- Lower construction cost than other alternatives

## DISADVANTAGES

- Eastbound B-loop off-ramp less desirable than other configurations with increased collision risk;
   Less desirable left turns required for southbound movements to Highway 401 eastbound and westbound
- resulting in increased collision risk and potential for operational issues;
- Reduced intersection / access spacing south of Highway 401 relative to other options
   Displacement of commercial property in southeast quadrant

## DESCRIPTION:

- Parclo AB interchange configuration with westbound B-loop off-ramp

  Basis ment of County Boad 32 to the cost for staging of replacement

  Output

  Description of the cost for staging of replacement

  Output

  Description of the cost for staging of replacement

  Output

  Description of the cost for staging of replacement

  Output

  Description of the cost for staging of replacement

  Output

  Description of the cost for staging of replacement

  Output

  Description of the cost for staging of replacement

  Output

  Description of the cost for staging of replacement

  Description of the cost for staging of the cost for stage of the cost for staging of the cost for stagin
- Realignment of County Road 32 to the east for staging of replacement structure

## ADVANTAGES

 Improved weaving distance along Hwy 401 EB and WB between Thousand Islands Pkwy and County Road 32 ramps relative to other options;

**ALTERNATIVE 5 - PARCLO AB TO WEST** 

Impacts to natural environment generally limited to west side of interchange

## DISADVANTAGES

- Westbound B-loop off-ramp less desirable than other configurations with increased collision risk;
   Left turns required for porthbound to eastbound and westbound movements resulting in increased.
- Left-turns required for northbound to eastbound and westbound movements resulting in increased collision risk and potential for operational issues;

## 

